District Forest Officer's decision in the assessment of damages will be final and the assessed damages will be recovered from the security deposit of the contractor.

(*h*) That the required quantity of fuel is cut and removed on prepaid licenses only from the plot selected and marked by the Range Officer.

(*i*) That for breach of any or all of the conditions of the contract by the contractor or his agents, employees or workmen the contract shall be null and void at the option of the District Forest Officer and that the latter may, after issuing to the contractor a notice of cancellation of contract, enforce forfeiture of all or any part of deposit and resell the right or work it departmentally at the risk of the contractor as in clause (1) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

Note.—Interest at 6¼ per cent per annum will be levied on all arrears of amounts which are permitted to be paid after the due date.

H. S. RANGACHAR,
District Forest Officer.

KADUR FOREST DIVISION.

Abstract Notification, dated the 13th June 1936.

The attention of the public is invited to the Notification calling for Tenders for the purchase of the exclusive right of collecting the Minor Forest Produce on all Government unoccupied lands, Amrit Mahal Kavals, State Forests, Reserve Lands and Plantations for two years from 1st July 1936 to 30th June 1938 in Chikmagalur Taluk, published on page 901, Part VI of the *Mysore Gazette*, dated the 18th June 1936.

A. V. KESAVIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT

KOLAR DIVISION.

Notification dated 24th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 27th July 1936, for restoration of breached Kolimpalli Sunnapralakere, Register No. 795, Minor, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (Two hundred) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoration of breached Kolimpalli Sunnapralakere, Register No. 795, (Minor) Bagepalli Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Progress to the extent of Rs. 600 has to be shown every month.

Abstract estimate for restoring Kolimpalli Sunnaparlakere, Register No. 795, Bagepalli Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	I. Bund at R. L. 55.00, Top width 4½′ side slope 1½ : 1 and 2 : 1.				
1	Jungle clearing by roots	Grade	2 0 0	8	
2	Cutting grips and trenches to bund for the receipt of new earth	,,	2 0 0	8	
3	Earthwork to bund with watering and consolidation	C.yd.	0 4 0	2,812	
4	New stone revetment	,,	1 12 0	500	
5	Turfing the slopes	,,	0 0 9	2,488	
6	Removing and resetting old stone work with new jelly	,,	0 8 0	390	
7	Providing and fixing new grade stone including figuring	Each	1 8 0	16	
8	Do Index stones do	,,	0 6 0	16	
9	Do B. M. Stones do	,,	3 0 0	2	
10	Do Register No. and date stones	,,	3 0 0	1	
11	Do Grade stones do	,,	15 0 0	1	
	II. Breach Filling.				
1	Clearing site and debris and baling water, etc., complete	L. S.	..	..	
2	Cutting vertical grovers at sides of old bund	C.yd.	0 3 0	163	
3	Clearing site in breach	,,	0 3 0	167	
4	Benching rock for core wall	S.ft.	0 8 0	172	
5	Burnt stone in surki mortar	C.ft.	0 5 0	516	
6	Providing puddle wall	C.yd.	0 12 0	106	
7	Filling in breach with equal portions of gravel and clay including watering and consolidation	,,	0 6 0	1,695	
8	Turfing the slopes of breach	S.yd.	0 0 9	683	
9	Gravel backing	C.yd.	0 6 0	93	
10	New stone work	C.yd.	1 12 0	205	
	III. Constructing a cast iron pipe sluice 7″ in diameter with cill at R. L. 42.00.				
1	Cut opening the bund and refilling with consolidation	C.yd.	0 5 6	119	
2	Earthwork excavation for foundation	,,	0 3 0	5	
3	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 3	120	
4	Burnt stone in surki mortar	,,	0 5 0	342	
5	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 5 0	83	
6	Pointing with cement mortar	Sqr.	4 8 0	4.53	
7	Providing plug and rod with locking arrangements	L. S.	..	..	
8	Drilling holes in slabs	,,	..	..	
9	Supplying and fixing cast iron pipes 7″ in dia. including Ry. freight, carting charges, etc., complete	R.ft.	3 0 0	36	
	IV. Constructing a masonry weir 125 feet long with crest at R. L. 50.00.				
1	Clearing site and boulders	L. S.	..	..	
2	Earthwork excavation	C.yd.	0 3 0	471	
3	Stone jelly concrete in surki mortar	C.ft.	0 4 3	288	
4	Burnt stone in surki mortar	,,	0 5 0	642	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
5	Burnt stone slab 6" thick dressed and fixed ..	S.ft.	0 5 0	595	
6	Pointing swith cement mortar	Sqr.	4 8 0	10.22	
7	Rough stone work new	C.yd.	1 12 0	45	
8	Providing joggle joints	Each	0 12 0	15	

N. SUBBA RAO,
Executive Engineer.

MYSORE DIVISION.

Notification dated 29th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M., on 20th July 1936 for Deviation of Nanjangud-Hassanurghat Road in Chamaraj Nagar Town through Parivarakere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a depoist of Rs. 375 (three hundred and seventy-five) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Deviation of Nanjangud-Hassanurghat Road in Chamarajnagar Town through Parivarakere" in default of which, the tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract of quantities for the deviation of Nanjangud-Hassanurghat Road in Chamarajnagar Town through Parivarakere.

No.	Items of work	Per	Quantity	Rate	Cost	Rate tendered
				Rs. a. p.	Rs.	
1	Earthwork to embankment, etc., including watering, tamping etc., complete	C.yd.	3,153	0 4 0	788	
2	Carting earth with lead of ½ a mile ..	,,	3,153	0 3 0	591	
3	Opening drains and using earth to embankment including watering and tamping	,,	496	0 4 0	124	